BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

APPROVED SCHEDULE - B

Name of the Work : Finishing Work to Anganavadi Building at Kodigehalli in Ward No. 08, Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	KRIDL	
				In Figures	In Words
1	612.47	Providing and fixing M.S. grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery etc complete as per specifications and directions of engineer in charge of the work.	Kgs	95.40	Rupees Ninety Five and Forty Paise Only
2	47.56	Providing and laying flooring 40mm thick, with an under layer of 30mm thick 1:2:4 cement concrete, using broken granite metal of 12.5mm nominal size and top layer of 10mm thick plaster with cement mortar 1:3, finished with a floating coat of neat cement , including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	442.02	Rupees Four Hundred Forty Two and Two Paise Only
3	215.11	Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc complete as per specifications and directions of engineer in charge of the work	Sqm	1456.44	Rupees One Thousand Four Hundred Fifty Six and Forty Four Paise Only
4	12.60	Providing and fixing in position collapsible steel stutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5 cms openings at 10 cms. c to c applying a priming coat of re lead paint, cost of materials, labour, HOM of machinery complete as per specifications. Size of gate 2.4mx1.4m etc complete as per specifications and directions of engineer in charge of the work	Sqm	4306.78	Rupees Four Thousand Three Hundred Six and Seventy Eight Paise Only
5	40.05	Providing and laying flooring using pre polishing water cut/gang saw 19 mm thick Granite slab over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement / colour pigment etc., complete. **using grey granite** etc complete as per specifications and directions of engineer in charge of the work	Sqm	2067.00	Rupees Two Thousand Sixty Seven Only

Signature of the Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	KRIDL	
				In Figures	In Words
6	14.93	Providing skirting, dado, rises of steps with **Colour glazed tiles 30x45cms 6mm thick** on withborder of size 30x10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	Sqm	1261.40	Rupees One Thousand Two Hundred Sixty One and Forty Paise Only
7	10.30	Providing Ceramic tiles of size 30 x 30 Cms approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, etc complete as per specifications and directions of engineer in charge of the work	Sqm	933.86	Rupees Nine Hundred Thirty Three and Eighty Six Paise Only

I am prepared to execute the above mentioned work written by me in Schedule - B

Contractor Signature
Reg. No.
Postal Address

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92